

I claim:

1. A method of enclosing an area, comprising the steps of:

- 5           a. providing at least one screening member,
- b. providing at least one removable shelf; and
- c. horizontally supporting said at least one removable shelf with said screening member
- such that the screening member and said at least one shelf are configured to enclose the area.

10    2. The method of claim 1, wherein said screening member is planer.

3. The method of claim 1, wherein said screening member comprises drywall.

4. The method of claim 1, wherein said screening member is removable.

15    5. The method of claim 1, wherein said at least one removable shelf is horizontally supported

through frictional engagement with the screening member and an existing wall.

6. The method of claim 1, wherein said at least one removable shelf is horizontally supported

20    through frictional engagement between two screening members.

7. A shelving unit, comprising:

a screening member; and

at least one removable shelf in contact with and horizontally supported by said screening member, wherein the screening member and said at least one shelf are configured to enclose an area.

8. The unit of claim 7, wherein said screening member is planar.

9. The unit of claim 7, wherein said screening member comprises drywall.

10. The unit of claim 7, wherein said screening member is removable.

11. The unit of claim 7, wherein said at least one removable shelf is horizontally supported through frictional engagement with the screening member and an existing wall.

12. The unit of claim 7, wherein said at least one removable shelf is horizontally supported through frictional engagement between two screening members.

13. A shelving unit, comprising:

at least two screening members; and

at least one removable shelf in contact with and horizontally supported by said screening members, wherein the screening members and said at least one shelf are configured to enclose an area.

14. The unit of claim 13, wherein said shelving unit further includes a door disposed in front of said at least one removable shelf.

15. The unit of claim 13, wherein said screening member is planer.

5

16. The unit of claim 13, wherein said screening member comprises drywall.

17. The unit of claim 13, wherein said screening member is removable.

10 18. The unit of claim 13, wherein said at least one removable shelf is horizontally supported through frictional engagement with the screening member and an existing wall.

19. The unit of claim 13, wherein said at least one removable shelf is horizontally supported through frictional engagement between two screening members.

15

20. The unit of claim 13, further including a removable back member in contact with said screening members and disposed between said at least one removable shelf and said area.